Sr No	Panel Watt	NOS of Modules	Total kW	Price with GST	System Cost With GST	Meter Charges	PPA & MCB Charges	First Quotation	Subsidy	After Subsidy
1	540	4	2.16	54,861	118,500	5,000	1,000	124,500	62,880	50,620
2	540	5	2.7	51,667	139,500	5,000	1,000	145,500	72,600	61,900
3	540	6	3.24	50,000	162,000	5,000	1,000	168,000	78,000	79,000
4	540	7	3.78	50,000	189,000	5,000	1,000	195,000	78,000	106,000
5	540	8	4.32	50,463	218,000	5,000	1,000	224,000	78,000	135,000
6	540	9	4.86	51,029	248,000	5,000	1,000	254,000	78,000	165,000
7	540	10	5.4	49,630	268,000	5,000	1,000	274,000	78,000	185,000
8	540	11	5.94	48,485	288,000	5,000	1,000	294,000	78,000	205,000
9	540	12	6.48	49,382	320,000	15,000	1000	336,000	78,000	258,000
10	540	13	7.02	50,926	357,500	15,000	1,500	374,000	78,000	285,000
11	540	15	8.1	52,099	422,000	15,000	1,500	438,500	78,000	349,500
12	540	18	9.72	48,302	469,500	15,000	1,500	486,000	78,000	397,000

## **Technical Specifications'**

COMPONENTS	ADANI/WAREE		
Solar PV Module	540+ Watt MONO Crystal		
HDG Structure 60mmx40mmx2mm 60MICRON	SURYA/HINDUSTAN		
On Grid Inverter	K Solare /Havells /Any reputed		
DCDB/ ACDB	Havells/L&T/C&S		
Isolator	Havells/L&T/C&S		
Earthing Kit with Lightning Arrester	CBR 14 mm/1.25 METER 4 SPICK		
GI HD4 Box Pipe -60x40x2mm, ISI	Surya/TATA/L&T/HINDUSTAN		
MC4 Connector	Standard		
PVC Pipe	25" WHITE ISI Stander		
DC Cable 1C 4 sqmm FLECIBLE Cooper	PolyCab/KE/RR Kabel		
AC Cable 1C 4 sqmm flexible Cooper	PolyCab/KE/RR Kabel		
Earthing Cable- 4 sqmm flexible Cooper	PolyCab/KE/RR Kabel		
LA CABLE- 16sq mm Aluminum	PolyCab/KE/RR Kabel		
Pipe Saddle	PVC/Galvanized		

## **Required Documents**

- \* Latest Electricity Bill
- \* Aadhar Card
- \* Property Tax bill / Index-2 / Sale Deed
- \* Passport Size Photograph
- \* Pan card
- \* Cancelled Cheque

**Terms & Conditions** 

1 Shifting / relocation, rearrangement, or handling charges will be at actual if required during the warranty period.

2 The system will not be considered under warranty if any changes are made by customers after installation without information to the company.

**3 Project completion period 2 – 3 weeks after Technical Feasibility approval.** 

4 Considered single meter only in each location. Additional meter charges extra.

5 Quoted rates are inclusive of supply, erection, installation, commissioning, including all taxes.

6 Structure is considered standard for RCC roof, with a basic height from the lower end at 1500 mm from the roof. Any changes suggested by management will result in additional charges.

7 Subject to Ahmedabad jurisdiction.

8 Material dispatch 50% payment received

**Warranty Terms** 

**1** Inverter warranty: K Solare/SoLex/Solarium –5 year's manufacturer warranty.

2 Solar panel warranty: Solar modules will cover 25 years of performance up to 80% of generation

**3** Full system warranty: 5 years.

4 Exclusions from warranty: physical damages, acts of god, any destructive activities, improper handling will not be covered under warranty circumstances. Regular cleaning of the panel is not included in this contract.

**Payment Terms** 

\* Rs. 20,000/- Advance along with the purchase order / order confirmation, 40% on feasibility approval and Balance 50% on material dispatch.

\* Quotation is valid for 15 Days

\* Payment can be done by Cheque / NEFT / RTGS /UPI

\* Cheque to be issued in favor of "SuKarm " Kishor Somchand Mistry"